BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

APPROVED SCHEDULE –'B'

Name of Work:-Construction to roads and drains at Chikkabettahalli and surrounding areas in ward no:03

Sl	Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
1	KSRRB 300-1,Earth work excavation by manual means in ordinary soil involving an average horizontal throw up to 2 meters and an average lift uo to 1.5m,excavated surface levelled and sides neatly dresssed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications (Item no19.1,Page no143, PWD SR 2018-19)	Cum	1564.60	137.80	Rupees One Hundred Thirty Seven and Paise Eighty Only
2	KSRB 100-1 Loading and unloading ofstone aggregates / sand/ kanker/ Moorum /soil KSRRB M100-1 Placing tipper at loading with front end loader dumpting turning for return trip excluding time for haulged and return trip complete as per specification item No 17.1 page 130 and KSRB M.100.4.1 costof haulage excluding loading and unloading MORTH to a distance of 4.00 K.M (Item No 17.4 Page 136 (SR 2018-19)	Cum	1564.60	87.56	Rupees Eighty Seven and Paise Fifty Six Only
3	KSRB 4-1.3: Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.Specification No.KBS 4.1, 4.2 (P.12/I.4.3)/ PWD SR 2018-19	Cum	127.50	5408.12	Rupees Five Thousand Four Hundred Eight and Paise Twelve Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Yelahanka Division
Yelahanka Zone
Bruhat Bangalore Mahanagara Palike
BANGALORE 560064

	Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
	Providing and laying in position plain /reinforced cement concretefor side drains wall and bottom thickness 15 cm using M20 nominal mix concrete with OPC cement at 300 kg with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.43 cum machine mixed well completed for walls at bottom including centring shuttering cost of materials HOM of machineries curing etc., complete excluding cot of steel as per MORTH specification No:1500,1700,2200 Page No 271item No 37.59.2 PWD SR 2018-19	Cum	293.40	7070.20	Rupees Seven Thousand Seventy and Paise Twenty Only
5	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 Page No. 18/ Item No. 4.46/ PWD SR 2018-19	Qntl.	18.89	75223.96	Rupees Seventy Five Thousand Two Hundred Twenty Three and Paise Ninety Six Only
6	RCC Precast covering slab for drain (10 cm thick)	Sqm	729.00	2337.00	Rupees Two Thousand Three Hundred Thirty Seven Only
7	Providing precast slab of 250 mm thick including cost of all materials, labour, curing,transportation,loading ,unloading,etc.,complete as per the direction of engineer in charge-	Sqm	36.00	5418.00	Rupees Five Thousand Four Hundred Eighteen Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Signature of the Contractor

Executive Engineer
Yelahanka Division
Yelahanka Zone
Bruhat Bangalore Mahanagara Palike
BANGALORE 560064

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.